Sixfold
LAND & FIRE · MONUMENT, CO

(720) 772-6146
Contact@SixfoldColorado.com

SERVICES AS OF 25 AUG 2026
EL PASO · DOUGLAS · TELLER · THE FRONT RANGE FOOTHILLS

Tree work and fire mitigation — what we do

Hand and saw work on defensible space, from the wall out to the property line — and the written record that lets the state and your insurer pay toward some of it. **Every estimate is free and in writing.**

Trees

STANDING TIMBER, ONE AT A TIME OR BY THE STAND

Felling
Dropping a tree where there is room to drop it.

Full tree removal
The whole tree gone — felled, limbed, bucked and cleared off the property.

Full tree trimming
Crown raising, deadwood out, branches off the roof and back from the chimney. The **6–10 ft** of clearance the defensible space guidance asks for.

Ground fuels

THE LAYER THAT CARRIES FIRE UP INTO THE TREES

Full brush removal
Undergrowth, ladder fuels, ground juniper and Gambel oak taken out from under the canopy.

Landscaping
Putting the ground back once the fuel is off it — including the non-combustible surfacing the first five feet around a house is supposed to have.

By the acre

DEFENSIBLE SPACE · HAND AND SAW WORK, ZONES 1 AND 2

Defensible space around the home
The full acre worked to Colorado State Forest Service spacing — crowns apart, ladder fuels gone, the first five feet stripped.

Thinning by the acre
Lightly wooded or heavy forest, priced and scheduled by what is actually standing on it.

What happens to the wood

YOUR CALL — AND THE CHOICE THAT MOVES A QUOTE MOST

Slashing
Cut down and stacked into piles where you point, or lopped and scattered. Kept **30 ft or more** from the house either way.

Chipping
Run through the chipper on site. Chips spread, heaped where you want them, or taken away.

Left on site
Cut to rounds and stacked, or left where it falls. Green wood needs a season before it burns.

Ask before we start. **What happens to the material is usually the biggest single number in any quote**, and most companies fold it in without saying so.

The paperwork

TWO PARTIES WILL PAY TOWARD THIS WORK — BOTH WANT IT DOCUMENTED

Support with the state tax credit
An itemised invoice that separates the qualifying vegetation work, a written scope, and before-and-after photographs — what the claim needs attached. **We cannot file your return and this is not tax advice**; whether you qualify is your accountant's call.

Help with your insurance premium
Since **1 July 2026** a Colorado insurer using a wildfire risk score must tell you the score, what drove it, and what each mitigation action would do to it — and you can ask for a re-score after work is done. We give you the record to send them. **The insurer decides what it is worth**; we cannot promise a discount.

> **This is what the current crew and kit can take on, as of 25 August 2026.** A working list, not a fixed scope — written from what is in the truck today, not from what we are willing to quote. If what you need is not on it, ask.

Where the work happens

COLORADO STATE FOREST SERVICE DEFENSIBLE SPACE ZONES, MEASURED FROM THE WALL OF EACH STRUCTURE

ZONE 1 · 0–5 FT

Strip it
Brush removal and landscaping. Nothing that burns against the wall — no shrubs, no mulch, no wood stored.

ZONE 2 · 5–30 FT

Thin it
Felling, removal and trimming. Crowns **10 ft** apart, branches up **6–10 ft**, ladder fuels out.

ZONE 3 · 30–100 FT

Open it
Thinning by the acre. Crowns **6–10 ft** apart with real gaps, and the woody debris taken off rather than scattered.

GETTING STARTED

Estimates are free and written. We walk the property, agree the scope, and the price is fixed before a saw starts — it doesn't move unless you add work.

YOUR PROTECTION

Sign at your home and you have three business days to cancel — in writing, any reason, no fee. Colorado law, and not waivable. We don't start until those days have run.

Tell us what you want gone. We'll come and look.

(720) 772-6146 · call or text · Contact@SixfoldColorado.com